

Caution!

- 1. Ensure that all components have sufficient load-bearing capacity! Observe all information provided by the respective manufacturer!
- 2. Riggers must have received specialized training!
- 3. For transport, all degrees of freedom of the container must be secured appropriately in all directions!
- 4. Adhere to the applicable load safety regulations!

max. 35 t

The container itself weighs up to 35 t.

Lashing material is provided by the customer or the forwarding company.

Slings:


- Length: approx. 4 m

Alternatively, use the twistlock system to mount the container directly to the container chassis (20 feet) of the truck. In this case, the control cabinet side of the container (the side with additional ISO corners and doors) must face into the opposite direction of the truck's driving direction.

Angle to plumb line on the clamping plane: approx. 30°

DETAIL A (1 : 10)

Place anti-slip mats below all 10 support points!

 FENECON		FENECON GmbH Gewerbepark 6 94547 Iggenbach Deutschland		Diese Zeichnung ist unser geistiges Eigentum und darf ohne unsere Zustimmung nicht vervielfältigt oder an Drittpersonen sowie Wettbewerber weitergegeben werden.	
Name		Signatur		Datum	
Gezeichnet				23.10.2025	
Geprüft				23.10.2025	
Genehmigt				23.10.2025	
Produktion					
				Maßstab: 1:30	
				Material: -	
				Gewicht: max. 35t	
				Oberfläche: -	
Kanten DIN ISO 13715				Projekt: Industrial XL	
				ERP-Nummer: -	
				A3	

Zeichnungsnummer: IXL-239-01-01

Titel:
IXL Container Transport Instructions

